



#### NOTES:

1. OVER EXCAVATION REQUIRED WHEN UNSUITABLE FOUNDATION MATERIALS ENCOUNTERED.
2. STRICTLY COMPLY WITH ALL TRENCH SAFETY SYSTEM REQUIREMENTS.
3. RESTRAINED JOINT PIPE MAY BE REQUIRED AS DIRECTED BY THE DISTRICT.
4. BACKFILL TRENCH IN ACCORDANCE WITH SNOHOMISH COUNTY ENGINEERING DESIGN AND DEVELOPMENT STANDARDS AND CVWD STANDARD DETAIL TBR-1.

**CROSS VALLEY WATER DISTRICT  
TRENCH BACKFILL AND RESTORATION**

**UNSUITABLE FOUNDATION  
EXCAVATION**

TBR-3

NOT TO SCALE

FEB 2022