



**NOTES:**

1. WATER METER AND DOMESTIC SERVICE LINE SIZES TO BE APPROVED BY DISTRICT
2. FIRE SPRINKLER PLANS TO BE REVIEWED AND APPROVED BY DISTRICT ENGINEER PRIOR TO UNLOCKING METER
3. INSTALLATION TO BE INSPECTED BY DISTRICT
4. ALL MATERIALS TO BE LEAD FREE
5. IF FLOW-THROUGH SYSTEM IS USED ON FIRE LINE, THEN NO BACKFLOW PREVENTION DEVICE IS REQUIRED. A FIRE SYSTEM PLAN SHALL BE SUBMITTED TO WAIVE THE DEVICE REQUIREMENT.
6. NO CHEMICALS ALLOWED. BACKFLOW DEVICE IS TO BE TESTED AT INSTALLATION AND ANNUALLY THEREAFTER BY WASHINGTON STATE CERTIFIED TESTER. COPY OF TEST REPORT SENT TO WATER DISTRICT.

**CROSS VALLEY WATER DISTRICT  
STANDARD WATER DETAILS**

**RESIDENTIAL DOMESTIC AND  
FIRE SPRINKLER SYSTEMS  
OUTSIDE PIPING PLAN**

WD-6

NOT TO SCALE

FEB 2022